

PROJECT NAME: INFILTRATION AND INFLOW (I&I) REMEDIATION

PROJECT NUMBER: 0436T260

CLIENT: TOWNSHIP OF WINSLOW

Standard Pipe Services, LLC
 567 Walther Road
 Newark, DE 19702
 302-256-0701
 ((BB, CS, SS, etc.))

Mobile Dredging & Video Pipe
 1566 Harding Highway
 Newfield, NJ 08344
 856-697-1900
 ((BB, CS, SS, etc.))

#	DESCRIPTION	QUANTITY & UNITS		UNITS PRICE	TOTAL	UNITS PRICE	TOTAL
Contract #4: Eastmont Lane - Pipe Replacement							
1	MOBILIZATION (MAXIMUM BID AMOUNT IS PER NJAC 7:14-2.9; COPY ENCLOSED IN SPECIFICATIONS)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
2	PRE & POST CONSTRUCTION CLEANING & TELEVISIONING, 8-INCH SANITARY SEWER	620	LF	\$0.00	\$0.00	\$0.00	\$0.00
3	OPEN CUT - REMOVE DOUBLE BAG; HAUL AND DISPOSE OF EXISTING 8-INCH ACP SANITARY SEWER AND PROVIDE 8-INCH PVC SDR-35 SANITARY SEWER, 0 - 8' DEEP	32	LF	\$0.00	\$0.00	\$0.00	\$0.00
4	PROVIDE RECONNECTION OF PIPE TO EXISTING MANHOLE	1	UN	\$0.00	\$0.00	\$0.00	\$0.00
5	REMOVE EXISTING SANITARY SEWER LATERAL AND PROVIDE NEW 4" PVC LATERAL, DEPTH OF 8' OR LESS, FITTINGS,	50	LF	\$0.00	\$0.00	\$0.00	\$0.00
6	DEWATERING SYSTEM, COMPLETE	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
7	TRENCH STABILIZATION (IF & WHERE DIRECTED) (MIN. BID PRICE = \$6.00/CY)	15	CY	\$0.00	\$0.00	\$0.00	\$0.00
8	SELECT BACKFILL (IF & WHERE DIRECTED) (MIN. BID PRICE = \$6.00/CY)	75	CY	\$0.00	\$0.00	\$0.00	\$0.00
9	DENSE GRADED AGGREGATE BASE COURSE, 4" THICK (MIN. BID PRICE = \$5.00/SY)	50	SY	\$0.00	\$0.00	\$0.00	\$0.00
10	HOT MIX ASPHALT MIX 19M64, BASE COURSE, 6" THICK (MIN. BID PRICE = \$11.50/SY)	50	SY	\$0.00	\$0.00	\$0.00	\$0.00
11	MILL 2" AND OVERLAY WITH HOT MIX ASPHALT MIX 9.5M64, SURFACE COURSE, 2" THICK (MIN. BID PRICE = \$8.00/SY)	175	SY	\$0.00	\$0.00	\$0.00	\$0.00
12	ALLOWANCE, UNIFORM POLICE TRAFFIC CONTROL, IF & WHERE DIRECTED BY THE OWNER	40	HR	\$0.00	\$0.00	\$0.00	\$0.00
13	ENVIRONMENTAL & CULTURAL RESOURCE PROTECTION AND RESTORATION (MINIMUM LUMP SUM BID OF \$1,000.00)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
14	MAINTENANCE & PROTECTION OF TRAFFIC	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
5	TEST PITS FOR EXISTING LATERAL ALIGNMENT/DEPTH AT PROPOSED CLEANOUT	10	CY	\$0.00	\$0.00	\$0.00	\$0.00
16	NJEIT PROJECT SIGN	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
17	ALLOWANCE, ROAD OPENING / CONSTRUCTION PERMITS IF & WHERE DIRECTED BY THE OWNER	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
18	RESTORATIONS (MINIMUM LUMP SUM BID OF \$3,000.00)	1	LS	\$0.00	\$0.00		

R REMINGTON & VERNICK ENGINEERS
V BID TABULATION

PROJECT NAME: INFILTRATION AND INFLOW (I&I) REMEDIATION

PROJECT NUMBER: 0436T260

CLIENT: TOWNSHIP OF WINSLOW

Standard Pipe Services, LLC
 567 Walther Road
 Newark, DE 19702
 302-256-0701
 ((BB, CS, SS, etc.))

Mobile Dredging & Video Pipe
 1566 Harding Highway
 Newfield, NJ 08344
 856-697-1900
 ((BB, CS, SS, etc.))

#	DESCRIPTION	QUANTITY & UNITS	UNITS PRICE	TOTAL NO BID	UNITS PRICE	TOTAL NO BID
	TOTAL CONSTRUCTION COST					

R REMINGTON & VERNICK ENGINEERS
V BID TABULATION

PROJECT NAME: INFILTRATION AND INFLOW (I&I) REMEDIATION

PROJECT NUMBER: 0436T260

CLIENT: TOWNSHIP OF WINSLOW

Standard Pipe Services, LLC
 567 Walther Road
 Newark, DE 19702
 302-256-0701
 ((BB, CS, SS, etc.))

Mobile Dredging & Video Pipe
 1566 Harding Highway
 Newfield, NJ 08344
 856-697-1900
 ((BB, CS, SS, etc.))

#	DESCRIPTION	QUANTITY & UNITS		UNITS PRICE	TOTAL	UNITS PRICE	TOTAL
Contract #5: Evergreen Avenue - Pipe Replacement							
1	MOBILIZATION (MAXIMUM BID AMOUNT IS PER NJAC 7:14-2.9; COPY ENCLOSED IN SPECIFICATIONS)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
2	PRE & POST CONSTRUCTION CLEANING & TELEVISIONING, 8-INCH SANITARY SEWER	1170	LF	\$0.00	\$0.00	\$0.00	\$0.00
3	OPEN CUT - REMOVE EXISTING 8-INCH PVC AND PROVIDE 8-INCH PVC SDR-26, 0 - 16' DEEP	64	LF	\$0.00	\$0.00	\$0.00	\$0.00
3a	OPEN CUT - REMOVE EXISTING 8-INCH PVC AND PROVIDE 8-INCH PVC SDR-26, >16' DEEP	64	LF	\$0.00	\$0.00	\$0.00	\$0.00
4	PROVIDE RECONNECTION OF PIPE TO EXISTING MANHOLE	2	UN	\$0.00	\$0.00	\$0.00	\$0.00
5	REMOVE EXISTING SANITARY SEWER LATERAL AND PROVIDE 4" PVC SDR 26 LATERAL, DEPTH OF 16' OR LESS, FITTINGS, CLEANOUT, COMPLETE, IF & WHERE DIRECTED	40	LF	\$0.00	\$0.00	\$0.00	\$0.00
6	REMOVE EXISTING SANITARY SEWER LATERAL AND PROVIDE 4" PVC SDR 26 LATERAL, DEPTH OF >16', FITTINGS, CLEANOUT, CASTING, COMPLETE, IF & WHERE DIRECTED	40	LF	\$0.00	\$0.00	\$0.00	\$0.00
7	BYPASS PUMPING SYSTEM, IF & WHERE DIRECTED	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
7a	DEWATERING SYSTEM, COMPLETE	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
8	TRENCH STABILIZATION (IF & WHERE DIRECTED) (MIN. BID PRICE = \$6.00/CY)	50	CY	\$0.00	\$0.00	\$0.00	\$0.00
9	SELECT BACKFILL (IF & WHERE DIRECTED) (MIN. BID PRICE = \$6.00/CY)	550	CY	\$0.00	\$0.00	\$0.00	\$0.00
10	DENSE GRADED AGGREGATE BASE COURSE, 4" THICK (MIN. BID PRICE = \$5.00/SY)	400	SY	\$0.00	\$0.00	\$0.00	\$0.00
11	HOT MIX ASPHALT MIX 19M64, BASE COURSE, 6" THICK (MIN. BID PRICE = \$11.50/SY)	400	SY	\$0.00	\$0.00	\$0.00	\$0.00
12	MILL 2" AND OVERLAY WITH HOT MIX ASPHALT MIX 9.5M64, SURFACE COURSE, 2" THICK (MIN. BID PRICE = \$8.00/SY)	450	SY	\$0.00	\$0.00	\$0.00	\$0.00
13	ALLOWANCE, UNIFORM POLICE TRAFFIC CONTROL, IF & WHERE DIRECTED BY THE OWNER	40	HR	\$0.00	\$0.00	\$0.00	\$0.00
14	ENVIRONMENTAL & CULTURAL RESOURCE PROTECTION AND RESTORATION (MINIMUM LUMP SUM BID OF \$1,000.00)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00

R REMINGTON & VERNICK ENGINEERS
V BID TABULATION

PROJECT NAME: INFILTRATION AND INFLOW (I&I) REMEDIATION

PROJECT NUMBER: 0436T260

CLIENT: TOWNSHIP OF WINSLOW

Standard Pipe Services, LLC
 567 Waither Road
 Newark, DE 19702
 302-256-0701
 ((BB, CS, SS, etc.))

Mobile Dredging & Video Pipe
 1566 Harding Highway
 Newfield, NJ 08344
 856-697-1900
 ((BB, CS, SS, etc.))

#	DESCRIPTION	QUANTITY & UNITS		UNITS PRICE	TOTAL	UNITS PRICE	TOTAL
15	MAINTENANCE & PROTECTION OF TRAFFIC	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
16	NJEIT PROJECT SIGN	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
17	TEST PIT TO LOCATE UTILITIES	25	CY	\$0.00	\$0.00	\$0.00	\$0.00
18	NJPE SIGNED / SEALED DESIGN OF CONTRACTOR'S SITE SPECIFIC TRENCH PROTECTIVE SYSTEMS	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
19	REMOVAL AND REPLACEMENT OF 15" CMP STORM SEWER AT STATION 10+30 EVERGREEN AVENUE, IF AND WHERE DIRECTED	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
20	REMOVAL AND REPLACEMENT OF 15" CMP STORM SEWER AT STATION 13+21 EVERGREEN AVENUE, IF AND WHERE DIRECTED	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
21	ALLOWANCE, ROAD OPENING / CONSTRUCTION PERMITS IF & WHERE DIRECTED BY THE OWNER	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
22	RESTORATIONS (MINIMUM LUMP SUM BID OF \$4,000.00)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
TOTAL CONSTRUCTION COST						NO BID	NO BID

PROJECT NAME: INFILTRATION AND INFLOW (I&I) REMEDIATION

PROJECT NUMBER: 0436T260

CLIENT: TOWNSHIP OF WINSLOW

Standard Pipe Services, LLC
 567 Walther Road
 Newark, DE 19702
 302-256-0701
 ((BB, CS, SS, etc.))

Mobile Dredging & Video Pipe
 1566 Harding Highway
 Newfield, NJ 08344
 856-697-1900
 ((BB, CS, SS, etc.))

#	DESCRIPTION	QUANTITY & UNITS		UNITS PRICE	TOTAL	UNITS PRICE	TOTAL
Contract #6: South Cedarbrook Road - Manhole Replacement							
1	MOBILIZATION (MAXIMUM BID AMOUNT IS PER NJAC 7:14-2.9; COPY ENCLOSED IN SPECIFICATIONS)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
2	REMOVE AND REPLACE 4' DIAMETER SANITARY SEWER MANHOLE WITH 4' DIAMETER FLAT TOP MANHOLE WITH PVC LINER, INCLUDING CONNECTIONS TO EXISTING PIPING	1	UN	\$0.00	\$0.00	\$0.00	\$0.00
3	TEMPORARY BYPASS CONVEYANCE SYSTEMS, COMPLETE	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
4	ALLOWANCE, UNIFORM POLICE TRAFFIC CONTROL, IF & WHERE DIRECTED BY THE OWNER	72	HR	\$0.00	\$0.00	\$0.00	\$0.00
5	MAINTENANCE & PROTECTION OF TRAFFIC	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
6	NJEIT PROJECT SIGN	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
7	ENVIRONMENTAL & CULTURAL RESOURCE PROTECTION AND RESTORATION (MINIMUM LUMP SUM BID OF \$1,000.00)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
8	ALLOWANCE, ROAD OPENING / CONSTRUCTION PERMITS IF & WHERE DIRECTED BY THE OWNER	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
9	REMOVE AND REPLACE 8" PVC SDR 35 SANITARY SEWER MAIN BETWEEN MANHOLES #3 AND #4, INCLUDES CONNECTIONS TO ALL MANHOLES	10	LF	\$0.00	\$0.00	\$0.00	\$0.00
10	RESTORATIONS (MINIMUM LUMP SUM BID OF \$2,000.00)	1065	LS	\$0.00	\$0.00	\$0.00	\$0.00
TOTAL CONSTRUCTION COST					NO BD	NO BID	NO BID

PROJECT NAME: INFILTRATION AND INFLOW (&I) REMEDIATION

PROJECT NUMBER: 0436T260

CLIENT: TOWNSHIP OF WINSLOW

Standard Pipe Services, LLC
 567 Walther Road
 Newark, DE 19702
 302-256-0701
 ((BB, CS, SS, etc.))

Mobile Dredging & Video Pipe
 1566 Harding Highway
 Newfield, NJ 08344
 856-697-1900
 ((BB, CS, SS, etc.))

#	DESCRIPTION	QUANTITY & UNITS		UNITS PRICE	TOTAL	UNITS PRICE	TOTAL
Contract #7: Sassafra Court - Manhole Replacement							
1	MOBILIZATION (MAXIMUM BID AMOUNT IS PER NJAC 7:14-2.9; COPY ENCLOSED IN SPECIFICATIONS)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
2	REMOVE AND REPLACE 4' DIAMETER SANITARY SEWER MANOLE, INCLUDING CONNECTIONS TO EXISTING PIPING	1	UN	\$0.00	\$0.00	\$0.00	\$0.00
3	OPEN CUT - REMOVE EXISTING 8-INCH PVC AND PROVIDE 8-INCH PVC SDR-35, 0 - 8' DEEP	52	LF	\$0.00	\$0.00	\$0.00	\$0.00
4	TRENCH STABILIZATION (IF & WHERE DIRECTED) (MIN. BID PRICE = \$6.00/CY)	15	CY	\$0.00	\$0.00	\$0.00	\$0.00
5	SELECT BACKFILL (IF & WHERE DIRECTED) (MIN. BID PRICE = \$6.00/CY)	55	CY	\$0.00	\$0.00	\$0.00	\$0.00
6	DENSE GRADED AGGREGATE BASE COURSE, 4" THICK (MIN. BID PRICE = \$5.00/SY)	45	SY	\$0.00	\$0.00	\$0.00	\$0.00
7	HOT MIX ASPHALT MIX 19M64, BASE COURSE, 6" THICK (MIN. BID PRICE = \$11.50/SY)	45	SY	\$0.00	\$0.00	\$0.00	\$0.00
8	MILL 2" AND OVERLAY WITH HOT MIX ASPHALT MIX 9.5M64, SURFACE COURSE, 2" THICK (MIN. BID PRICE = \$8.00/SY)	70	SY	\$0.00	\$0.00	\$0.00	\$0.00
9	BYPASS PUMPING SYSTEM, IF & WHERE DIRECTED	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
10	ALLOWANCE, UNIFORM POLICE TRAFFIC CONTROL, IF & WHERE DIRECTED BY THE OWNER	24	HR	\$0.00	\$0.00	\$0.00	\$0.00
11	MAINTENANCE & PROTECTION OF TRAFFIC	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
12	NJEIT PROJECT SIGN	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
13	ENVIRONMENTAL & CULTURAL RESOURCE PROTECTION AND RESTORATION (MINIMUM LUMP SUM BID OF \$1,000.00)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
14	ALLOWANCE, ROAD OPENING / CONSTRUCTION PERMITS IF & WHERE DIRECTED BY THE OWNER	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
15	RESTORATIONS (MINIMUM LUMP SUM BID OF \$1,000.00)	1	LS	\$0.00	\$0.00	\$0.00	\$0.00
16	TEST PITS TO DETERMINE TOP OF EXISTING PIPE ELEVATIONS AT PROPOSED CONNECTION POINT WITH NEW PIPING	25	CY	\$0.00	\$0.00	\$0.00	\$0.00
17	POST CONSTRUCTION CLEANING AND TELEVISIONING, 8" SANITARY SEWER	900	LF	\$0.00	\$0.00	\$0.00	\$0.00
TOTAL CONSTRUCTION COST					NO BID		\$0.00